



मोतीलाल नेहरू कॉलेज Motilal Nehru College

(दिल्ली विश्वविद्यालय)
(University of Delhi)



संदर्भ : एमएनसी/बीजेएम

Ref. : MNC/BJM/2023/1546

Dated : 06.03.2023

SHORT TENDER NOTICE

FOR FIXING OF INTERLOCKING PAVER OUTSIDE CANTEEN AREA

Sealed tender are invited for fixing of interlocking paver outside Canteen area in Motilal Nehru College. Scope of work for the same is attached herewith.

Interested firms/companies may fill the prescribe format and should reach the college latest by 13th March, 2023 by 2.00 p.m.

On the top of the envelope, it should be written:

“Short tender for fixing of interlocking paver outside Canteen area”

The envelope should be addressed to :

The Principal
Motilal Nehru College
Benito Juarez Marg
New Delhi-110021.

Bidders should enclosed the following documents with the tender:

1. Firm/company registration certificate
2. Experience certificates/work completion/work orders etc. of last three years only.
3. Prescribe format duly completed in all respect.
4. Bank details
5. GSTIN as applicable.
6. 2% earnest money be deposited with the tender through Demand Draft in favour of Principal, Motilal Nehru College.

Terms & Conditions:

1. Warranty period will be 5 years, for any wear and tear contractor will provide services without any charges.
2. Completion of work shall be completed by 18th March, 2023.
4. Corrigendum/addendum, if any, will be posted on college website well in time.

Rajeshwar Sharma
06/03/2023
Acting Principal
Motilal Nehru College

MNC/BJM/2023/1546

SHORT TENDER FOR FIXING OF INTERLOCKING PAVER OUTSIDE CANTEEN AREA

N/W P/L inter locking paver block out side (sitting area) Canteen, Motilal Nehru College

S.No	Description	Qty	Unit	Rate	Amount
1	CONCRETE WORK				
1.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
1.1.1	1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources: 4 graded stone aggregate 20 mm nominal size derived from natural sources).	5	cum		
	Sub-Total				
2	REPAIRS TO BUILDING				
2.1	Disposal of malba	1	job		
	Sub-Total				
3	DISMANTLING AND DEMOLISHING				
3.1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.				
3.1.1	Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	15	cum		
	Sub-Total				
4	ROAD WORK				
4.1	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge.	1000	sqm		
	Sub-Total				
	Total				

Yogendra Sharma
06/03/2023

Acting Principal

Motilal Nehru College