MOTILAL NEHRU COLLEGE:BENITO JUAREZ MARG:NEW DELHI-110021

REFURBISHMENT OF THE BASKEETBALLCOURT (TENDER)

Short Tender Notice

Quotation for additional work ner basketball court the Motilal Nehru College is one of the affiliated colleges of the University of Delhi and is located in the south campus.

Seated offline tenders are invifed in the prescribed format given below, where the scope of work is given.

Interested firms / companies may fill the prescribe format and should reach the college latest by 28.2.2023 by 12.00 pm.

The envelop should have a covening letter with the experience certificate / work completion order attached along with the introduction of the firm/company. On the top of the envelop, it should be written.

Work adjoining to basketball court

The envelop should be addressed to:

The Principal
Motilal Nehru College
Benito Juarez Marg
South Campus
New Delhi – 110021

Enclosures:

1) Firm/company registration certificate
2) Experience certificates/Work completion/work order etc of last three years only.
3) Prescribe format duly completed in all respect .
4) Bank details
5) GSTIN (if applicable).

कार्यवाहक प्राचार्य
Officiating Principal
मोतीलाल नेहरू महाविद्यालय
Motilal Nehru College
(दिल्ली विश्वविद्यालय)
(University of Delhi)
बेनितो हुआरेज मार्ग
Benito Juarez Marg
नई दिल्ली–110021
New Delhi-110021

Additional worknear Basket Ball Court

S No	Work Description	Unit	Quantity	Rate	Amount
1	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : 6.4.1 Cement mortar 1:4 (1 cement : 4 coarse sand) cum 7809.25				
2	Cement mortar 1:4 (1 cement : 4 coarse sand)	Cub. Mtr	48		
3	12 mm cement plaster of mix :	SqrMtr.	180		
4	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand)				
5	25 mm thick	Sqr. Mtr	75		
6	Kota stone slabs 20 mm thick in risers of steps, skirting, dado and pillars laid on 12 mm (average) thick cement mortar 1:3 (1 cement: 3 coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slabs, including rubbing and polishing complete.	Sqr. Mtr	75		
7	Extra for pre finished nosing in treads of steps of Kota stone/ sand stone slab.	Mtr.	200		
8	Providing and laying C.C. pavement of mix M-25 with ready mixed concrete from batching plant. The ready mixed concrete shall be laid and finished with screed board vibrator , vacuum dewatering process and finally finished by floating, brooming with wire brush etc. complete as per specifications and directions of Engineer-in-charge. (The panel shuttering work shall be paid for separately).	Cub Mtr.	40		
9	Steel work in built up tubular (round, square or rectangular hollow tubes etc., MS angle, MS Plate) trusses etc., including cutting, hoisting, Half round turning ('D' Type Shaped) , fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.	KG	500		
10	Providing and fixing precoated galvanised steel sheet roofing accessories 0.50 mm (+ 0.05 %) total coated thickness, Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws complete .	SqrMtr	45		

मोती लाल नेहरू कॉलेज दिल्ली विश्वविद्यालय नई दिल्ली-110021

.1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	LS	1		
12	Constructing brick masonry road gully chamber 50x45x60 cm with bricks in cement mortar 1:4 (1 cement : 4 coarse sand) including 500x450 mm pre-cast R.C.C. horizontal grating with frame complete as per standard design : 19.27.1 With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	Each	9		
13	Providing and laying heavy quality 5" PVC pipe of approved makes as per	Mtr	80		
	Total				

कार्यवाहक प्राचार्य
Officiating Principal
मोतीलाल नेहरू महाविद्यालय
Motilal Nehru College
(दिल्ली विश्वविद्यालय)
(University of Delhi)
बेनिटो हुआरेज मार्ग
Benito Juarez Marg
नई दिल्ली–110021
New Delhi-110021