

# MOTILAL NEHRU COLLEGE: BENITO JUAREZ MARG: NEW DELHI

MNC/BJM/2018/1009

Date : 09.10.2018

## QUOTATION NOTICE

Sealed quotations are invited for the following renovation work in the Canteen area of the College. The details of the same are as under:-

S.No.	Description of Work	Area (Approx)	Rate Rs.
1	Dismantling of 9 inch front wall of canteen kitchen and removal of rubbish from the site or as directed. Approx wall area.	200 Sq. Ft.	
2	Dismantling of Kota stone on flooring and slabs including braking and removing complete all as directed.	One Job.	
3	Taking out cement plaster from wall including scribing down with water and making key for new plaster for fixing of tiles.	One Job.	
4	Dismantling of roof of the washroom/store area and fixing of water tank as directed.	One Job	
5	Removing of asbestos roof sheet and taking down with all necessary accessories etc complete.	One Job.	
6.	Making of brick wall approx size 10X15 ft. and 9 inch thick with essential foundation and provision of door and window etc. complete.	200 Sq. Ft.	
7.	Material and Labour for cement plaster with cement mortar 1:4 on wall including making surface even and smooth without using extra cement.	500 Sq. Ft.	
8.	Material and labour for ceramics wall tiles of size 12X15 inch (approx) dark shade as approved, including 15 mm plaster in cement mortar 1:4 complete in all as directed.	1000 Sq. Ft.	
9.	Material and labour for granite 18 mm thick (black), over 15 mm in cement mortar 1:4 and molding polishing on all outer edges complete in all as directed.	100 Sq. Ft.	
10	Material and labour for Kota stone 25 mm thick, 15 mm in cement mortar 1:4 and rubbing, polishing on surface complete in all as directed.	80 Sq. Ft.	
11	Material and Labour for fixing of profile sheet (metro) hut type on the kitchen of the canteen including brick work, steel work etc. the pipes required for sheet work will be used old pipe available in the College.	650 Sq. Ft.	
12	Material and labour for granite 60X24 inch, 18 mm thick (black), on the damaged tabled table top after repairing/welding of edges as required complete in all as directed.	05 Jobs	
13	Supply & fixing of over head water tank after removing the existing broken tank 2000 Ltr. Including all necessary fittings like gate ball/ball cock and connections etc. complete.	02 Nos	
14	Painting work : Two or more coats of plastic paint (Burger/Nerolac) on internal surface after repair of damaged walls by the Birla putty of the existing Canteen area etc. complete.	3000 Sq. Ft.	



15	Painting work : Two or more coats of enamel paint (Burger/Nerolac) on steel and wooden surface (door/window etc.) area in the existing Canteen area	500 Sq. Ft.	
16	Painting work: Two or more coats of all whether/exterior paint (Burger/Nerolac) on external surface after repair of damaged walls of the existing Canteen area etc. complete.	3500 Sq. Ft.	
17	Material and Labour for R.C.C. roof with cement, concrete 1:2:4 including steel reinforcement shuttering finishing, water proofing etc of existing pattern etc. complete.	200 Sq. Ft.	
18	Material and Labour for concrete work 1:2:4 (cement, sand & concrete)	50 Sq. Ft.	
19	After completion work all rubbish should be removed from the site.	One Job	

You may also enclose a copy of PAN number of your firm along with the quotation. Please write top of the envelop **"Quotation for Canteen Renovation"**. For further details, inspection of site etc. you may visit the College canteen on all working days between 10.00 a.m. to 5.00 p.m.

**Term & Conditions:-**

1. The rates should be included all the taxes/GST/Freight etc.
2. Payment will be made by RTGS/NEFT within 15 days after completion of work. All payment will be subject to deduction of taxes at source as per applicable rules.
3. Completion of work within 15 days from the placement of Purchase Order by the College.
4. Quotation should reach to Principal, Motilal Nehru College, Benito Juarez Marg, New Delhi-110021 through Registered/Speed post or dropped in the Box available in the Office latest by **20.10.2018 up to 3.00 p.m.. & the same will be open on 22.10.2018 at 11.00 a.m.**
5. The bidders are strictly required to attach a copy of GST/VAT registration certificate of the firm, with PAN number of the firm/owner otherwise bid/quotation will be deemed rejected.
6. In complete/conditional quotation will not be accepted.
7. On inspection, if the material or workmanship is not found as per the specification or any item is found damaged the same shall be rejected. In case of rejection of the materials, no payment will be made for the rejection item.
8. In the event of any dispute arising between the parties hereafter referred as Motilal Nehru College and Supplier/Dealer in respect of or connected with this quotation in all such matters the venue of proceedings will be Delhi and only Delhi or appropriate Courts will have jurisdiction over the same.
9. Principal, Motilal Nehru College reserves the right to accept or reject any or all offer without assigning any reason thereof.

  
Acting Principal

Copy to : Delhi University & College website.



Date \_\_\_\_\_

Authorized Signature & Stamp of firm/Co.