



Motilal Nehru College

(University of Delhi)

Ref. : MNC/BJM/303

Benito Juarez Marg,
New Delhi-110021

Date :

17.05.2014

Sealed quotations are invited for making of photostate-cum-stationery Room in the College. The details of the room are enclosed. You may also enclose a copy of PAN number and profile of your firm along with the quotation. Please write top of the envelop "**Quotation for Room**". Your quotation should reach to the under signed latest by 24.05.2014 up to 03.00 p.m. For further details you may visit the College in all working days between 10.00a.m. to 3.00 p.m.


17.5.14
Officiating Principal

Encl : As above

MOTILAL NEHRU COLLEGE : BENITO JUAREZ MARG : NEW DELHI-21

MNC/BJM/2014/303

DATE : 17.05.2014

QUOTATION FOR PHOTOSTATE-CUM-STATIONERY ROOM

S.No.	Description of Work	Rate in Rs.
1	The room with base area 18'0" X 13'0" having platform of size 18'0" X 3'0" in front leveled with and matched finishing to existing pathway. All walls to be 9" thick brick work (6:1) with standard foundation and necessary RCC linter over level of doors & windows as per direction.	
2	Roof to be covered with G.I. corrugated sheet (20 gage) placed over required purlins etc. complete.	
3	Thermally insulated false ceiling by mineral board 600X600mm including channels & suspended & making cut out for light fittings and fans etc. complete as used in jubilee block of the College.	
4	01 No Flush Door of 6'-0" X3'-0" size including M.S frame, (40X40X6mm) including all fittings and painting.	
5	02 Nos. window counters of min-size 4'0"X3'0" protected with M.S. grill as per design coupled with operable (5mm) acrylic sheet shutter on M.S. Section with all fittings and painting etc. complete.	
6	Base of counters to be made with marble stone (granite) 1'6" wide placed on RCC slab 2" thick (1:2:4).	
7	Plinth to be filled with compacted soil and white sand as required.	
8	Floor of Room to be finished with grey artificial stone (1:2:1) with cement scurry over 4" the mat concrete (1:4:8).	
9	All external wall to be cladded with grey grit-wash plaster (15mm) thick over cement-sand base (4:1) as per existing grit wash.	
10	All internal walls to be 15mm thick cement sand (1:6) plaster finished with 2 or more coats of O.B.D. paints after birla putty on all inner surface.	
11	Plinth protection of room for 3 side and provision for rain water drain in the outlet pipeline etc. complete.	
12	Electrical wiring for 02+1 light and 02 ceiling fan and four switch + socket (15 amp.) and 02 switch + socket 06 amp. In the room.	
13	The work should completed in 30 days after assigning of job order.	